

E-Enquiry Notice

MSETCL invites bids for following E-enquiry through inviting sealed quotation process of MSETCL in single bid system from registered contractors, agencies on Mahatransco website <http://mahatransco.in> for following works.

Sr. No.	E-enquiry No & Description of Work		Due date & Time (Hrs.) for submission & opening of E-Enquiry	
1.	Enquiry No. CELDK/ Maint/FM-16/2026-27/2422 dt.26.10.2026			
	Scope of Work: Supply and installation of 12 Nos. of work stations on 1st Floor including modular work stations; drawers; electrical, telephone & data sockets along with raceways and chairs at MSLDC, Airoli		Download/Purchase of Enquiry Documents Date: From 27.10.2026 to 02.11.2026	
	Estimated Cost (Rs)	Enquiry Fee	Closing Date (Submission)	Opening Date
	Rs. 7,11,014/-	NIL	02.11.2025 15.00 Hrs.	03.11.2026 (If possible)

Contact Person: Additional Executive Engineer (Maint)/Assistant Engineer (Maint) State Load Dispatch Centre, Thane-Belapur Road. At & Post Airoli Navi Mumbai - 400708.
Tel. no. 9320844448/8879963312

For further details visit our website <http://www.mahatransco.in>

Sd/-
(Milind Deole)
Superintending Engineer (SCADA/Admin)
MSLDC, MSETCL, Airoli.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.
CIN NO. U40109MH2005SGC153646

Office of The Chief Engineer
Maharashtra State Load Dispatch Center, Opp- Thane-Belapur Road, P.O. Airoli,
Navi Mumbai Pin – 400 708.
Tele :+91-22-27601931 / 2937; Fax :+91-22-27601769
Email: cesldc@mahasldc.in
website: <http://www.mahasldc.in>

Ref: CELDK/Maint/FM-16/2422

Date: - 26.10.2026

E-Enquiry

To,

All Vendors

Sub: Invitation of Quotations in sealed envelope for work of supply and installation of 12 Nos. of work stations on 1st Floor including modular work stations; drawers; electrical, telephone & data sockets along with raceways and chairs at MSLDC, Airoli

Dear Sir,

Quotations are invited in sealed envelope from experienced parties/contractors for following work at MSLDC, Airoli on or before 02.11.2026 up to 15:00 Hrs. with following terms and conditions.

Work: Supply and installation of 12 Nos. of work stations on 1st Floor including modular work stations; drawers; electrical, telephone & data sockets along with raceways and chairs at MSLDC, Airoli.

Terms & Conditions:

Terms & Conditions:

1. Scope of Work:

Rates shall be quoted for the **supply and installation of 12 Nos. of work stations on 1st Floor at MSLDC, Airoli**, including modular work stations, drawers, electrical sockets, telephone & data sockets, raceways, chairs and all associated accessories as per the specifications and quantities given in **Annexure-A**.

2. Rates:

Quoted rates shall be **firm and inclusive of all charges**, including transportation, loading/unloading, labour, tools & tackles, duties, taxes, tolls, installation charges and all other incidental expenses, complete in all respects. Nothing extra shall be paid on any account over and above the quoted rates. Any amount due to variation in statutory taxes and duties shall be reimbursed at actual, subject to submission of documentary evidence/bills and approval of the Competent Authority.

3. Period of Completion:

The entire work shall be completed **within 30 days from the date of issue of the work order**.

4. Quality and Execution:

You shall supply and install the work stations and associated items strictly as per the specifications, approved makes, dimensions, quantities and instructions given by this office. The modular work stations, drawers, chairs, electrical/telephone/data sockets, raceways and other materials shall be of **good quality and from reputed manufacturers**. The work shall be executed in a neat, safe and workmanlike manner to the satisfaction of the Engineer-in-Charge.

5. **Quantity:**

The quantity of **12 Nos. of work stations** shall be supplied and installed as per the requirement given in **Annexure-A**. Any change in quantity, if required, shall be carried out only with prior approval of the Competent Authority.

6. **Site Measurement / Inspection:**

The contractor shall inspect the site and verify the actual dimensions, layout, access, existing electrical/data/telephone points and other site conditions before quoting the rates. No claim arising due to failure to inspect the site shall be entertained.

7. **Validity:**

The validity of the quotation shall be **at least 30 days** from the last date of submission of quotation.

8. **Payment:**

Payment shall be made after **successful supply & installation of the complete work** by MSLDC, Airoli. The contractor shall submit the bill along with necessary supporting documents and completion/acceptance certificate. **No advance payment shall be made.**

9. **Security Deposit:**

Before taking the work in hand, the contractor shall pay **Security Deposit equivalent to 5% of the order value** in the form of BG/FDR, as applicable. The Security Deposit shall be refunded after **one year from satisfactory completion of the work**, subject to compliance with all terms and conditions of the order. In case of unsatisfactory performance, defective work, non-compliance with the terms and conditions or failure to rectify defects, the Security Deposit shall be liable for forfeiture.

10. **Damage to MSETCL/MSLDC Property:**

If any damage or loss occurs to MSETCL/MSLDC property, building, furniture, electrical installations, equipment, cables, flooring or any other property during execution of the work, the same shall be **made good/repaired/replaced by the contractor at his own cost** to the satisfaction of the Engineer-in-Charge.

11. **Transportation, Labour and Tools:**

No extra charges shall be paid towards **transportation, loading/unloading, labour, tools & tackles, shifting, installation, fixing, consumables or any other material/work required for satisfactory completion of the work**. All such arrangements shall be made by the contractor at his own cost.

12. **Taxes and Statutory Deductions:**

Income Tax, GST TDS and any other applicable statutory deductions shall be deducted from the contractor's bill as per the prevailing rules and rates.

13. **Documents to be submitted along with Quotation:**

The following documents shall be submitted along with the quotation:

- Copy of PAN Card.
- Certificate of Registration / MSME Certificate / Intimation under Maharashtra Shops & Establishment Act, 2018, if applicable.
- GST Registration Certificate, if applicable.
- Duly signed **Site Visit Report** by the Addl. Executive Engineer / Superintending Engineer.
- Similar type of work experience for **supply and installation of modular work stations, furniture, electrical/data/telephone sockets, raceways and chairs**, costing not less than **40% of the estimated cost**, i.e. **Rs. 2,84,406/-**, executed during any one of the previous five financial years.
- Copies of relevant Purchase Orders / Work Orders and Completion

Certificates in support of the above experience.

- If any document is not applicable, an undertaking to that effect shall be submitted, duly certified by the appropriate authority.

14. Dispute:

In case of any dispute arising out of or in connection with the work order, the decision of the **Competent Authority/undersigned shall be final and binding** on the contractor.

15. Penalty:

If the complete material is not supplied and installed within the stipulated period, a penalty of **½% of the order value per week**, subject to a maximum of **10% of the order value**, shall be levied at the discretion of the Competent Authority.

16. Cancellation of Quotation:

The undersigned shall have the right to **accept or reject any or all quotations, wholly or partly, without assigning any reason thereof.**

17. Late Quotations:

Quotations received **after the due date and time** shall not be accepted.

18. Standard Terms & Conditions:

The contractor shall abide by the **MSETCL standard terms and conditions applicable to work contracts**, in addition to the terms and conditions specified herein.

19. Safety:

The contractor shall be responsible for maintaining all necessary safety precautions during execution of the work. The work shall be carried out without causing obstruction or disturbance to the normal functioning of MSLDC, Airoli. All safety precautions shall be followed as per the instructions of the Engineer-in-Charge.

20. Removal of Debris and Cleaning:

After completion of the work, the contractor shall remove all packing materials, waste, debris and other unwanted materials from the work site and hand over the area in a **clean and usable condition**, at no extra cost to MSLDC.

21. Warranty/Defect Liability:

The supplied furniture, work stations, chairs, electrical/data/telephone accessories and other items shall be free from manufacturing and workmanship defects. Any defect noticed during the warranty/defect liability period shall be rectified/replaced by the contractor **at his own cost**, within the time stipulated by MSLDC.

22. Completion:

The work shall be considered complete only after **successful supply, installation, testing and satisfactory inspection of all 12 Nos. of work stations and associated items**, including electrical, telephone and data sockets, raceways, drawers and chairs, and after obtaining satisfactory completion confirmation from the Engineer-in-Charge.

Sd/-

(Milind Deole)

**Superintending Engineer (SCADA/Admin)
MSLDC, MSETCL, Airoli**

Annexure-A

Supply and installation of 12 Nos. of work stations on 1st Floor including modular work stations; drawers; electrical, telephone & data sockets along with raceways and chairs at MSLDC, Airoli.

Sr. No.	Description	Qty	Rate	Amount
1	STAFF OFFICE TABLE 1200 x 600 x 750 Providing and fixing of Modular table of required size. Table top shall be made of 25mm thick Marine ply (IS 710: 2010) laminate on all sides / surfaces. Sides in 18mm Marine ply (IS 710: 2010). All boards components like top, sides etc. are finished with 2mm thick machine pressed PVC edge banding in matching color. (Rehau Make/ or Equivalent) for better impact resistance. Other components like modesty panels of 600mm height (apron) shall be made of 18mm thick Marine ply (IS 710: 2010) in approved color and shade as per pre-approved sample etc. complete.	12 Nos.		
2	Drawer - Providing and supplying Modular Pedestal unit with 3 drawers of required shape and size, 560 x 450 x 650 mm LxWxH. Top made of 18mm thick Marine ply (IS 710: 2010), having post formed decorative laminate of 0.8mm on top and 0.6mm balancing laminate on unexposed face. Sides in 18 mm both side Pre laminate Particle boards (Interior Grade) and back made of 9mm thick both side prelaminated particle board, finished with 2 mm thick machine pressed PVC edge band on all edges etc. complete. Width of drawer unit shall be of standard size of 450mm. Drawer tray shall be of 12 mm thick Marine ply (IS 710: 2010) bottom included, of size suitable to accommodate telescopic glides for smooth operation. All visible edges of drawer trays shall have 2mm thick edge banding to match the color of the fascia. Inside edge of trays shall have 0.8mm thick PVC edge banding to match the color of the tray. Front Central lock to be provided for locking all drawers with all necessary hardware fittings, castors, handles etc. complete.	12 Nos.		
3	Chair - Providing and supplying chair having size Depth- 62cm, width-55cm, height-80cm & seat height 45 cm. (+/- 2cm), having seat & back, shall be made up of 1.2 cm hot pressed plywood, approved tapestry up to Rs.300/m and mold polyurethane foam with P.V.C. lipping all around etc. complete. The chair shall be provided with two-piece armrest made of polypropylene. The chair shall be supported by cantilever type powder coated tubular frame dia 2.54cm x 14 B G M.S.E.R.W. tube. All aluminum steel component shall have Epoxy Polyester Powder Coated. The chair shall be Ergonomic Dry film thickness shall be more than 45 Micron. And as directed by Architect in charge. The overall appearance of the product shall be as per photograph. All metal work shall be Epoxy Polyester Powder Coated and as directed by Architect in charge. VM 25132	12 Nos.		
Total				
18% GST				
Total with GST				

Sd/-
(Milind Deole)
Superintending Engineer (SCADA/Admin)
MSLDC, MSETCL, Airoli